



PART BASEMENT PLAN

1/8" = 1'-0"




FIFTH FLOOR PLAN UNIT "C"



FIFTH FLOOR PLAN UNIT 'D'

1/8" = 1'-0"



RETURN WATER END

SECTION

SUPPLY WATER END

REVISED FINNED PIPE DETAILS  
ROOMS C-511 thru C-516 AND D-510 thru D-512

Scale 1/2 Full Size.

PUMP SCHEDULE

Pump No.	Deliver GPM	FT Head	Motor HP	Valve Phase	Control Device	Remarks	Manufacturer Model No.
CP-4	22	55	1	200-34	Mag Str.	Bronze Fitted	Ball & Gossett 60-1 1/2 A
CP-5	20	34	1	11	Mag Str.	"	"
CP-6	22	34	1	11	Mag Str.	"	"
CP-7	26	37	1	11	Mag Str.	"	"

Finned Pipe Schedule

FP-1 1/2" composed of double tier 2 1/2 x 5 1/4 x 1 1/4" size to produce 1750 BTU per foot at 190°F water, GSF or 17500 BTU/hr total length of 10 ft for 17500 BTU/hr  
FP-2 composed of single tier 4 1/4 x 4 1/4 x 1 1/4" size to produce 1160 BTU per foot at 190°F water, GSF or 11600 BTU/hr total length of 10 ft for 11600 BTU/hr All existing may be reused  
Total existing approx 70 ft. Units welded together with not over 2" of fins missing