Construction Contracts Administration, Procurement Contracts & Materials Management (PCMM)
Oregon State University
644 SW 13th Ave.
Corvallis, Oregon 97333

P 541-737-4261
F 541-737-5546
oregonstate.edu

1/18/2019

Oregon State University
Construction Contract Administration
Campus ADA Restroom Upgrades

ADDENDUM NO. 1

THIS ADDENDUM IS BEING ISSUED for clarification and/or revisions of the drawings and specifications as noted. This document is hereby made a part of the Contract Documents to the extent as though it was originally included herein.

Item 1 Estimates for the four facilities involved in this project are as follows (provided for informational purposes):

- Covell Restroom: $56,000
- Gilbert Restrooms and Custodial Closet: $80,000
- Nash Restrooms: $48,000
- Langton Ramp and Handrails (inclusive of Alternate No. 1): $123,000

The following changes shall be made to the **TECHNICAL SPECIFICATIONS**:

Item 2 Reference Section 01 11 00 1.06; replace the sketch of the Langton Hall temporary accessible ramp with the attached sketch. See attached.

Item 3 Reference Section 05 52 00 Metal Railings 1.02 A.; replace "03 30 00 Concrete" with "03 00 00 Concrete".

Item 4 Reference Section 07 92 00 Joint Sealants 1.02 E.; replace "Section 09 65 00" with "Section 09 65 16".

Item 5 DELETE Section 08 71 00 Door Hardware in its entirety. Replace with the attached Section 08 71 00 Hardware (Add. 01).

Item 6 Reference Section 09 65 16 Resilient Sheet Flooring and Base 1.02 A.; replace "Section 09 06 01"" with "Section 09 06 00".

Item 7 Reference Section 09 91 00 3.06; replace I as follows:

I. Exterior Steel Handrails and associated components

1. Refer to Section 05 52 00 for powder coated finish.

SUBSTITUTION REQUESTS:

The following products have been properly submitted and approved substitutions. By use of these products in the Work, the Contractor agrees that: 1) The substitute product does not affect dimensions shown on the Drawings. 2) The Contractor will pay for changes to the building design, including engineering design, detailing and construction costs caused by the substitute product. 3) The substitute product will have no adverse effect on other trades, the construction schedule, or specified warranty requirements. 4) Maintenance and service parts will be locally available for the substitute product. 5) The function, appearance, and quality of the substitute product is equivalent or superior to the specified item.

Item 8 Reference Sheet E0.2; add the following approved manufacturer at the Luminaire Schedule:

Description	Manufacturer	Response
Fixture L1: 2GTL-4-60L-SWL-GZ10-LP840	Lithonia	Approved Manufacturer
Fixture L2: CLX-L48-4000LM-SEF-RDL-120-GZ10-40K-80CRI-WH	Lithonia	Approved Manufacturer

Item 9 Reference Section 09 51 00 2.02 C.2 and 2.03 B; add as an approved substitute for new suspension systems Rockfon Chicago Metallic Seismic Standard and as an approved substitute for new acoustic units Rockfon Medical Standard, respectively.

Item 10 Reference Section 22 40 00 2.03 A and B; add the following approved manufacturer. See Attached.

Description	Manufacturer	Response
Water Closet WC-1	Sloan	Approved Manufacturer
Urinal U-1	Sloan	Approved Manufacturer
Lavatory L-1	Sloan	Approved Manufacturer

The following changes shall be made to the **DRAWINGS**:

Item 10 Reference Sheets A1.1, A2.1 and A3.1, General Plan Notes; General Plan Notes 3 and 4 are in error and refer to Sheet T1.2 instead of Sheet A0.1; make this correction at these locations.

Item 11 Reference Sheet M0.1; Revise tag number “C-2” to “C-1”, revise manufacturer & model from “TITUS PAR” to “TITUS 50F”.

Item 12 Reference Sheet E0.2; Remove luminaire type L1X from the Luminaire Schedule.

Item 13 Reference Sheet E1.1; at Detail 7: Change the luminaire type from L1X to L1.

Item 14 Reference Sheet E1.1; at Detail 8: Change the luminaire type from L1X to L1.

Item 15 Reference Sheet E3.1; at Keyed note 8: Change “PANEL 2A4” to “PANEL 2C2”.

Item 16 Reference Sheet E3.1; at Keyed note 9: Change “PANEL 3A4” to “PANEL 3D2”.

END OF ADDENDUM NO. 1