



**Oregon State
University**

**Construction Contracts
Administration, Procurement
Contracts & Materials
Management (PCMM)**
Oregon State University
644 SW 13th Ave.
Corvallis, Oregon 97333

**P 541-737-3401
F 541-737-5546
oregonstate.edu**

5/30/2019

Oregon State University
Construction Contract Administration
ITB 199053 – MERRYFIELD HALL RENOVATION RE-BID

ADDENDUM NO. 9

THIS ADDENDUM IS BEING ISSUED for clarification and/or revisions of the Solicitation Documents as noted. This document is hereby made a part of the Solicitation Documents to the extent as though it was originally included therein.

ITEM NO. 1 Included with this addendum are Addendum 9 items as provided by Benchmark Architectural Services (dated 5/30/2019).

END OF ADDENDUM NO. 9

BENCHMARK ARCHITECTURAL SERVICES

2897 FIRWOOD PL. S.E., ALBANY, OREGON 97322 PHONE/FAX (541) 704-0619, benchmark@proaxis.com

May 30, 2019

Mr. Matt Hausman
Mr. Dave Raleigh
Oregon State University
Construction Contracts Administration
130 Oak Creek Building
Corvallis, Oregon 97331

Subject: OSU Merryfield Hall Renovation Project ReBid
Addendum #9

Dear Matt and Raleigh,

In response to a bidders questions it has been determined that the following clarifications shall be incorporated into the bidding documents:

1) Question:

Spec 232213 3.1 LP Steam Piping Applications – Specifies only threaded joints. Are welded fittings approved for use on this project for sizes 2-1/2" and up or are these joints and fittings to be flanged/threaded?

Response:

Welded joints are approved for use on this project for sizes 2-1/2" and up.

2) Question:

Note 4 on M3A says to replace existing steam piping below floor. Should this include condensate piping below floor?

Response:

The condensate piping below the floor shall be replaced as part of the project scope.

Please include this information in the next Addendum released and contact me if you have any questions or if you require any additional assistance at this time.

Sincerely,

Gary Day

Attachments:

None