

# ITB #2025-018906 HOVLAND HALL WEST WING REMODEL CONSTRUCTION SERVICES ADDENDUM NO. 2

ISSUE DATE: July 10, 2025

#### **CONTRACT ADMINISTRATOR:**

Matt Hausman, Construction Contracts Officer Construction Contracts Administration Email: ConstructionContracts@oregonstate.edu

This Addendum is hereby issued to inform you of the following revisions and or clarifications to the above-referenced Solicitation Document and/or the Contract Documents for the Project, to the extent they have been modified herein. Any conflict or inconsistency between this Addendum and the Solicitation Document or any previous addenda will be resolved in favor of this Addendum. Proposals shall conform to this Addendum. Unless specifically changed by this Addendum, all other requirements, terms and conditions of the Solicitation Document and or Contract Documents, and any previous addenda, remain unchanged and can be modified only in writing by OSU. The following changes are hereby made:

#### **BID DUE DATE/TIME**

Item 1 The Bid Due Date/Time has been extended to July 17, 2025, at 2:00 PM PT.

#### **SUPPLEMENTAL INFORMATION**

Item 2 Asbestos Building Inspection report has been added to the box link for RFP EXHIBIT 1 (https://oregonstate.box.com/s/5duegrxb1mpwzfk3xt3l5ra7bg27nkvm)

#### QUESTION/ANSWER

Item 3 Included with this addendum are responses to all questions asked prior to the deadline.

#### **CHANGES/CLARIFICATIONS**

Item 4 Included with this addendum are Changes/Clarifications to the Project Manual & Drawings from RBA dated 7/9/2025.

END OF ADDENDUM NO. 3

HOVLAND (	006	
QUESTION	QUESTION	OSU RESPONSE
1	Does the above request have an estimated or desired substantial completion date?	SEE ADDENDUM 1
		No, they are not OFOI. The Laboratory Table (LT) will be CFCI.
		Specification is on 123553.2.04 and Basis of Design,
2	   Section 2.04 – Modular Laboratory Tables (LT) – Please confirm if these tables are owner furnished	specification & size. Quantities are on sheet 1/A-800
	Section 2.06 – Adjustable Wall Shelves - Is SEFA painted steel wall shelving with seismic rails by the	ingingited on yellow. But shows to total
	casework manufacturer (to match casework) an acceptable alternative to plastic laminate wall	Due to the sodering that the stake holder will be using, please
3	shelving? Is a substitution request required?	stick with the specified metal shelving.
		No, they are not OFOI. The Sheet Good Strage Rack will be CFCI. Specification is on 123553.2.08, that shows the Basis of
	Section 2.08 – Sheet Good Storage Rack – Please confirm if this item is owner furnished and owner	Design, size number of bays & specs. Quantities are on sheet
4	installed. If not, please confirm location and quantity.	1/A-800 highlighted on yellow. But shows 1 total
		No, they are not OFOI. The Sheet Good Strage Rack will be CFCI. Specification is on 123553.2.09, that shows the Basis of
	Section 2.09 – Heavy-Duty Free-Standing Shelving - Please confirm if this item is owner furnished	Design, size number of bays & specs. Quantities are on sheet
5	and owner installed. If not, please confirm location and quantity.	1/A-800 highlighted on yellow. But shows 2 total
		No, they are not OFOI. The Sheet Good Strage Rack will be
		CFCI. Specification is on 123553.2.09, that shows the Basis of
6	Section 2.10 – Bin-Storage System - Please confirm if this item is owner furnished and owner	Design, size number of bays & specs. Quantities are on sheet
ь	installed. If not, please confirm location and quantity.	1/A-800. But shows 2 total
7	Is there a bid bond required?	No
		Yes, you can get in the building through the south access during
		the day and I will make sure the doors are unlocked up until bid
8	Is it possible to get access into the building again?	time. But they will be locked on the 4th of July.
	A-111 Keynote C1 describes an integrated shelf below the basins: OFCI. This is found again on A-	
	601 Keynote A-016, but appears for it to be CFCI and references to plumbing. Plumbing drawings,	See revised keynotes on A-111 and A-601, and revised notes in
9	specs and fixture schedule don't seem to indicate the integral shelf.	the Plumbing Fixture Schedule on P-002.
	It appears the drying rack may conflict with the S-1 faucet and attachment to wall (faucet	
10	submittal attached for reference)	Please see revised elevation 17/A-601.
11	. Will there be a virtual bid opening? If so, please provide link.	No
12	. Given the 4th of July holiday, we suggest an extension of the bid date.	SEE ADDENDUM 2
13	Is a bid bond required?	No
	Is a first-tier disclosure required at bid time? ITB's CapCon MWESB Subcontractor Report indicates	
14	First Tier reporting. What is the basis of determining first-tier sub contractors?	No
15	Is this project subject to Davis Bacon wage rate requirements?	No
	For BOLI rates, is the January 5th, 2025 rate book (and April amendments/apprentice rates) the	
16	wage rate basis?	SEE ITB SECTION 6.0
		The Hazard Materials Study of Hovland from 2008 has been
		added to the box link for Exhibit 1 in the RFP. OSU will be
17	Is an achectos survey report available?	responsible for all removal of Hazard Materials necessary for
1/	Is an asbestos survey report available?	contractors to complete their work on this project.
10	Are badging/background checks required?	No
18	Are badging/background checks required?  Spec sections 07 6200, 09 2116, 09 5100, and 09 9124 refer to delegated design in spec sections 01	No
	4000 and 01 6211. Spec sections 01 4000 and 01 6211 are not found in the specifications manual	References to delegated design in the spec are omitted.
19	for this project. Please provide.	Reference the Memo
·		Interior Work 6:00am to 7:00pm and Exterior Work 7:00am to
		7:00pm with the City ordinance. OSU will be happy to
20	What are the available work hours?	accomidate hours outside of this if it's included in your proposal.
	The state of the s	F F
		Please see revised keynotes A-005 and A-006 on A-111.
		Finished floor slopes should be installed to ¼" per foot max.
		Existing trench drains can be assumed to be -4" below the finish
		floor elevation, for the purpose of estimating floor levelling
21	% to trenches for quantifying floor leveler?	amounts. This shall be field verified by the Contractor.
		Please see revised keynote A-006 on A-111. Existing trenches
		have been decommissioned and filled. However, the Contractor
22	Will trenches (Keynote A-006/A-111) require de-commissioning and infill as well?	shall plug any existing drains which are exposed during below- slab work.
		JIGO WOLK.
22	A-001 indicates interior wall types as wood framed (W2 and W2A). Addendum 1 1/A-111 calls out	Disease see registed shoot & 2004 with add 1
23	wall type W1. Please provide wall assembly for Wall Type W1.	Please see revised sheet A-001 with added wall type.

9 July 2025



ROWELL BROKAW

1203 Willamette Suite 210 Eugene, Oregon 97401 541 485 1003 rowellbrokaw.com

Architecture. Design. Strategy

OSU Hovland Dry Lab Remodel

### Addendum # 03

#### 1 GENERAL ITEMS

None

#### 2 CHANGES AND CLARIFICATIONS TO THE PROJECT MANUAL

- 1) Section 07 6200 Sheet Metal Flashing and Trim. Revise as follows:
  - a) At Article 3.04 Field Quality Control, **DELETE** Paragraph A in its entirety.
- 2) Section 09 2116 Gypsum Board Assemblies. Revise as follows:
  - a) At Article 1.02 Related Requirements, **DELETE** Paragraph A in its entirety.
- 3) Section 09 5100 Acoustical Ceilings. Revise as follows:
  - a) At Article 1.02 Related Requirements, **DELETE** Paragraph A in its entirety.
  - b) At Article 1.05 Submittals, **DELETE** Paragraph B. Subparagraph 1. in its entirety.
- 4) Section 09 9124 Painting. Revise as follows:
  - a) **DELETE** Article 3.04 Field Quality Control in its entirety.

#### 3 CHANGES AND CLARIFICATIONS TO THE DRAWINGS

- 5) Sheet A-001 (re-issued, attached). Revisions include:
  - a) Framing size notes revised as shown.
  - b) Wall type W1 / W1A added as shown.
  - c) Drawing #3 Suspended ACT Diagram added as shown.
- 6) Sheet A-111 (re-issued, attached). Revisions include:
  - a) Keynotes A-005, A-006 and C1 revised as shown.
- 7) Sheet A-601 (re-issued, attached). Revisions include:
  - a) Keynotes revised as shown.
  - b) Elevation 17 revised as shown.
- 8) Sheet P-002 (re-issued, attached). Revisions include:

a) Plumbing fixture schedule revised as shown.

#### **4 SUBSTITUTION REQUESTS**

None

#### **5 BID QUESTIONS / ANSWERS**

**Question**: 3/A-111 indicates floor leveling and concrete pourback. Is there an available estimated slope grade % to trenches for quantifying floor leveler?

**Response:** Please see revised keynotes A-005 and A-006 on A-111. Finished floor slopes should be installed to  $\frac{1}{4}$ " per foot max. Existing trench drains can be assumed to be -4" below the finish floor elevation, for the purpose of estimating floor levelling amounts. This shall be field verified by the Contractor.


**Question**: Will trenches (Keynote A-006/A-111) require de-commissioning and infill as well?

**Response**: Please see revised keynote A-006 on A-111. Existing trenches have been decommissioned and filled. However, the Contractor shall plug any existing drains which are exposed during below-slab work.

#### **ATTACHMENTS**

- 1. Sheet A-001
- 2. Sheet A-111
- 3. Sheet A-601
- 4. Sheet P-002

End of Addendum-03




## 1. NOT ALL WALL CONFIGURATIONS ILLUSTRATED ON ASSEMBLIES SHEET ARE PRESENT IN THIS PROJECT. COORDINATE WALL TAGS IN DRAWINGS WITH CONFIGURATIONS SHOWN HERE. 2. WALL ASSEMBLIES WHERE NOTED AS FIRE RATED SHALL CONFORM TO CONFIGURATIONS AS NOTED IN GA FILE, UL FILE, ESR, OR OTHER TESTED ASSEMBLY INFORMATION. 3. FIRE RATING LISTED ON ASSEMBLY DRAWINGS IS THE MAXIMUM FIRE RATING ACHIEVABLE FOR THAT ASSEMBLY. SOME WALLS HAVE BEEN CHOSEN FOR THEIR STC RATING AND MAY NOT BE REQUIRED PER CODE TO MEET THE FIRE RATING LISTED ON ASSEMBLIES. CHECK INTERIOR PARTITION TYPE TAG ON FLOOR PLANS FOR ACTUAL FIRE RATING. 4. ALL GYPSUM WALL BOARD (GWB) TO BE 5/8" TYPE X U.N.O. 5. "A" NOTE IN PARTITION AND EXTERIOR WALL TYPE DESIGNATION REFERS TO "ACOUSTIC". - AT INTERIOR "A" TYPE WALLS, PROVIDE SOUND ATTENUATION BLANKET. - AT "A" TYPE METAL STUD WALLS, STUDS TO BE 25GA OR 20G EQ (SCAFCO SUPREME D20 OR CLARK 6. SOUND ATTENUATION BLANKET TO BE THE FULL DEPTH OF STUD CAVITY U.N.O. 7. RESILIENT CHANNELS TO BE CLARK DIETRICH RC DELUXE (RCSD) OR CEMCO RC1-XD ONLY. 8. STOREFRONT SYSTEMS ARE CALLED OUT SEPARATELY FROM WALL TYPES AND ARE SCHEDULED ELSEWHERE IN THE DOCUMENT SET. 9. AT LOCATIONS NOTED TO HAVE WALL TILE FINISH, SUBSTITUTE CEMENTITIOUS BACKER BOARD FOR GWB AS TILE SUBSTRATE PER SPECIFICATIONS. 10. SEE FINISH SCHEDULE FOR WALL AND CEILING FINISHES. SEE INTERIOR ELEVATIONS AND FINISH SCHEDULE FOR TILE EXTENTS. 11. "PRIMARY" LAYER IS THE LAYER AT THE FACE OF STUD. FLOOR, ROOF, & CEILING TYPE TAG INTERIOR PARTITION TYPE TAG LOCATION OF TAG INDICATES SIDE OF PARTITION TYPE WALL TO RECEIVE ADDITIONAL LAYERS OF GYP WHEN INDICATED BY THE PARTITION FIRE RATING / PARTITION (EXCEPTION: SHAFT WALLS SH1 & SH2 HEIGHT DESIGNATION -TAGGED @ SHAFTLINER SIDE OF WALL) STUD FRAMING / CMU SIZE DESIGNATION ADD-03 **→#**} WOOD FRAMING SIZE DESIGNATION 1 = 1X (3/4" FURRING) $\mathcal{E}_2 = 2X2 (1 1/2")$ $\geq 3 = 2 \times 3 (2.1/2")$ $\mathcal{E}_4 = 2X4 (3.1/2")$ ∂6 = 2X6 (5 1/2") $\geq 8 = 2 \times 8 (7.1/4'')$ (10 = 2X10 (9 1/4") FIRE RATING / PARTITION HEIGHT DESIGNATION B.O. STRUCTURE CEILING LINE \_\_\_\_\_\_ - COLOR FILL @ 1HR RATED WALLS COLOR FILL @ 2HR RATED COLOR FILL @ 3HR RATED - ^ + 0 1 2 3 : PARTIAL HEIGHT PARTITION. SEE PLAN AND ELEVATIONS FOR SPECIFIED ^: NON RATED TO B.O. CEILING +: NON RATED. EXTEND STUDS TO B.O. STRUCTURE ABOVE. EXTEND GYP BOARD 6" ABOVE TOP OF CEILING U.N.O. 0 : NON RATED. EXTEND STUDS TO B.O. STRUCTURE ABOVE. EXTEND GYP. BOARD BOTH SIDES TO B.O. STRUCTURE ABOVE U.N.O. 1: (1) HOUR FIRE RATED ASSEMBLY 2: (2) HOUR FIRE RATED ASSEMBLY 3: (3) HOUR FIRE RATED ASSEMBLY **ACOUSTIC PARTITIONS** PARTITION WALL TYPES THAT END WITH AN "A" DESIGNATION, ARE ACOUSTIC WALLS. THESE ARE NOTED VISUALLY IN PLAN WITH A HONEYCOMB HATCH. IF RATED, THE WALL SHOWS BOTH ACOUSTIC AND FIRE RATING HATCH.

**GENERAL NOTES - WALL TYPES** 

# ROWELL BROKAW

1203 Willamette Street Suite 210 Eugene, Oregon 97401 541 485 1003 rowellbrokaw.com

Architecture. Design. Strategy.



REVISIONS TO THIS SHEET
REV. DATE DESCRIPTION

2 ADD-03

 SET ISSUE
 DATE

 100% SD SET
 2025-01-31

 BID SET
 2025-06-06

 PERMIT SET
 2025-06-24

PROJECT TRACKING

RBA #: 2434
P.I.C: AUSTIN BAILEY
PM / PA: PATRICK HANNAH

OWNER OREGON STATE

UNIVERSITY


Project Name
OSU HOVLAND DRY LAB

Project Address
2700 SW CAMPUS WAY.

2700 SW CAMPUS WAY, CORVALLIS, OR 97331

LEGENDS - NOTES -ABBREVIATIONS - WALL ASSEMBLIES

A-001



**GENERAL NOTES: REFLECTED CEILING PLANS** 

1. REFERENCE FINISH SCHEDULE FOR CEILING TYPES AND FINISHES.

2. SEE FLOOR PLAN FOR WALL TYPE CALL OUTS 3. REFERENCE MECHANICAL, ELECTRICAL, PLUMBING AND FIRE PROTECTION DRAWINGS FOR INFO ON MECHANICAL, ELECTRICAL, PLUMBING AND FIRE PROTECTION SYSTEMS AND EQUIPMENT.

- NOTIFY ARCHITECT OF ANY DISCREPANCIES BETWEEN THOSE DRAWINGS AND THE INFORMATION SHOWN ON THE ARCHITECTURAL RCP. 4. SEE ELECTRICAL SHEETS FOR LIGHTING SCHEDULES AND ADDITIONAL FIXTURE LOCATIONS. 5. SEE MECHANICAL SHEETS FOR AIR SUPPLY, RETURN, AND EXHAUST DUCT ROUTING.
- 6. FOR REQUIRED CEILING GRID SEISMIC BRACING SEE TYPICAL SUSPENDED CEILING DETAIL. 7. WHERE NOTED, "OPEN TO STRUCTURE" ROOM AREA HAS NO CEILING MATERIAL. 8. LIGHTING - FOR ROOMS WITH A SINGLE LIGHT FIXTURE, CENTER FIXTURE WITHIN ROOM U.N.O. 9. EXIT SIGNS NOT SHOWN. REFERENCE ELECTRICAL DRAWINGS.

# **CEILING TYPE KEY**

MATERIAL TYPE ACT ACT-1 - 2 x 4





MOUNT LARGE MECH.

UNIT ON NEW EQUIP. PAD

CONC. EQUIPMENT PAD.

REF. MECHANICAL FOR

(E) STAIR STRUCTURE.

MOUNT SMALL MECH. UNIT ON (E) EQUIP. PAD


CEILING MOUNTED HOOD

REF MECH.

FINAL PAD SIZE.

REF. DETAIL: 2 / A-301

VFY LAYOUT.



ADD-03

16' - 7 1/2"

STORAGE A-010

A-003

1 L1 - FLOOR PLAN 1/8" = 1'-0"

RESOURCES-

13' - 5"

13' - 5"

A-004 0008-2

VESTIBULE/

L0007

VESTIBULE

**EXTERIOR** 

**LEGEND - EQUIPMENT** 

LASER CUTTER, OFOI.

CNC MACHINE, TORMACH, OFC

TEAM WORK

Key Value

### **WALL TYPES:**

SEE WALL ASSEMBLIES SHEET A-XXX FOR WALL TYPE INFORMATION.

## GENERAL NOTES: DIMENSION PLANS / FLOOR PLANS

6. PROVIDE SOLID 2X12 BLOCKING AT LOCATIONS OF WALL MOUNTED ITEMS.

1. ALL DIMENSIONS TO FACE OF FRAMING / MASONRY / CONCRETE U.N.O. 2. RATED WALL ASSEMBLIES TO BE CONTINUOUS AT WALL JOINS WITH NON-RATED WALLS. TYP. 3. COORDINATE WITH REFLECTED CEILING PLANS FOR SOFFIT AND TOP OF WALL DETAIL CALLOUTS. 4. PROVIDE DEFLECTION HEAD AT ALL FULL HEIGHT WALLS U.N.O. 5. OFFICE FURNITURE IS INDICATED FOR DESIGN CLARITY ON THE FLOOR PLAN WITH A DASHED


TRENCH DRAIN IS FILLED WITH CONCRETE. BUT SOME OPEN DRAIN LINE MAY REMAIN. FIELD VERIFY AND PLUG ABANDONED TRENCH DRAIN WHERE UNCOVERED.

STAINLESS SINK, 2 BASIN + 2 FAUCETS, DRAINBOARDS, EUL, LENGTH INTEGRATED SHELF BELOW DRAINBOARDS/BASINS, CUSTOM CONTRACTOR FURNISHED AND INSTALLED. REFERENCE PLUMBING.

# **ROWELL BROKAW**

1203 Willamette Street Suite 210 Eugene, Oregon 97401 541 485 1003 rowellbrokaw.com

Architecture. Design. Strategy.



**REVISIONS TO THIS SHEET** 

2 ADD-03 ADD-01

2025-06-24

SET ISSUE DATE

2025-01-31 100% SD SET **BID SET** 2025-06-06 2025-06-24 PERMIT SET

PROJECT TRACKING

P.I.C: **AUSTIN BAILEY** 

PM / PA: PATRICK HANNAH

**OREGON STATE** 

UNIVERSITY


Project Name **OSU HOVLAND DRY LAB** REMODEL

Project Address 2700 SW CAMPUS WAY,

CORVALLIS, OR 97331

FIRST FLOOR PLAN AND





ROWELL BROKAW

1203 Willamette Street Suite 210 Eugene, Oregon 97401 541 485 1003 rowellbrokaw.com

Architecture. Design. Strategy.

AUSTIN C. BAILEY
EUGENE, OREGON
LIC. #5702
STAMP

REVISIONS TO THIS SHEET
REV. DATE DESCRIPTION

2 ADD-03 2025-07-08 1 ADD-01 2025-06-24

SET ISSUE DATE

100% SD SET 2025-01-31
BID SET 2025-06-06
PERMIT SET 2025-06-24

PROJECT TRACKING

RBA #: 2434
P.I.C: AUSTIN BAILEY
PM / PA: PATRICK HANNAH

OWNER OREGON STATE

UNIVERSITY

Project Name

OSU HOVLAND DRY LAB
REMODEL
Project Address

Project Address
2700 SW CAMPUS WAY,
CORVALLIS, OR 97331

**INTERIOR ELEVATIONS** 

A-601


PLUMBING FIXTURE SCHEDULE													
<u>MARK</u>	Count	DESCRIPTION	MANUFACTURER	MODEL	W	CONNEC	TION SIZ CW	E HW	W	NIMUM E V	BRANCH S CW	IZE HW	NOTES
<u>EW-1</u>	1	WALL MOUNTED EYE WASH / DRENCH HOSE	Guardian Equipment	G5014			1/2"	1/2"			1/2"	1/2"	3
<u>S-1</u>	1	TWO COMPARTMENT SINK WITH DRAINBOARDS	ELKAY	2C24X24-2-24X	1 1/2"	1 1/2"	1/2"	1/2"	2"	2"	1/2"	1/2"	(1,2,4)
													$\sim\sim$

NOTES: 1 PRO

- PROVIDE SPLASH MOUNTED PRE-RINSE FAUCET WITH 2-3/8" INCH HANDLES, SIMILAR TO CHICAGO FAUCETS 510-G613L15XKCAB.
- INCLUDE TRAP, DRAIN AND ANGLE STOP VALVE. PROVIDE TRUEBRO P-TRAP AND VALVE COVERS FOR S-1.
- 3. PROVIDE G6020 THERMOSTATIC MIXING VALVE AND IN-LINE VACUUM BREAKER.

  4. PROVIDE FULL-LENGTH (98") INTEGRATED STAINLESS STEEL SHELF AT 12" AFF. PROVIDE STAINLESS STEEL LEGS WITH ADJUSTABLE BULLET FEET AT EACH END TO SUPPORT SHELF.

  ADD-03



# ROWELL BROKAW

1203 Willamette Street Suite 210 Eugene, Oregon 97401 541 485 1003 rowellbrokaw.com

ADD-03

Architecture. Design. Strategy.





REVISIONS TO THIS SHEET

REV. DATE DESCRIPTION

2 2025-07-07 ADD-03

SET ISSUE DATE

100% SD 2025-01-31
100% CDs 2025-06-06

PROJECT TRACKING

CBE #: 20240533

P.I.C: RJ

PM / PA: MK

OREGON STATE
UNIVERSITY

Project Name

OSU HOVLAND DRY LAB

Project Address
2700 SW CAMPUS WAY,

CORVALLIS, OR 97331

SCHEDULES AND DETAILS

P-002